

Note to File Nature HUB - Evaluation Results

On the 16th of January 2020, the MINARET evaluation committee signed below, have met in order to evaluate the received offers for the design and construction of a Nature Hub in Monastir municipality in Tunisia.

The evaluation was held against the following criteria, based on the requirements detailed in the call for bids.

Bidder	Technical Offer (Design, layout, features) 35%	Past Experience 15%	Financial Offer 50%	Final score 100%
Speed Cooling	Full	Full	Full	Full

the only Application

According to the above scores, the evaluation committee agrees to award the contract

Speed Cooling

to:

Motivation; please substantiate your scores to the winning bidder:

As the only bidder, Speed Cooling has been selected preliminarily under the condition of fulfilling the requirements presented in Annex 1 of the evaluation.

Evaluation Committee

Name	Organization	Signature
Rami El-Akhras (Chair)	MINARET	
Ahmad Hijazi	MINARET	
Manel Bin Ismail	Notre Grand Bleu	
Ahmed Souki	Notre Grand Bleu	
Kamal Nouira	Notre Grand Bleu	
Mustapha Bakir (Observer)	Notre Grand Bleu	



QUOTE

N°	SC8524
Date	14/01/2020

CLIENT : Notre Grand Bleu

MF : 1363741/F/P/N/000

**Adresse : résidence Kairouan Cap marina 5000
Monastir**

Block 1: Main Building // Bâtiment principal

Designation	Qty
Supply and installation and construction of a room of dimension (11.4m/6.4m/h2.8m) in treated and tinted light metallic structure and framework in red wood and OSB wood and rock wool layer which make the sound and heat insulation and aquatic and wisa composite wood with a total surface area of 145.92 m ² in the form of modules	01
COMPOSITION	
Ground floor (72.96m²) *open space *shower room *staircase FLOOR (72.96m²) *two research rooms with two sliding walls *kitchenette *two toilets	
WALL CLADDING	
-supply and installation and construction of the red wooden frames coated on the outside with 9mm thick OSB wood and on the inside with 50 mm rock wool. External and internal coating of the walls in wood (wisa or ash veneer) thickness 9mm treated and stained (colour according to the customer's choice). -supply and installation of a decorated false ceiling in wood (wisa/brake veneer) treated and stained.	
GROUND COVERING	
-floor in reinforced metal structure treated and tinted with injected polystyrene concrete covered with 9mm wisa wood flooring (treated and tinted).	
ALUMINIUM	
-supply and installation of single-glazed aluminium windows and doors (colour white). *open space: two windows of dimension(L1.5m*L1m) *Water room: window size (L0.4m*L0.4m) *Search room: dimension window(L1M*L1M). *main entrance door of dimension(L1.2M/L2.1M) * Sanitary block inlet door size (L0.8m*L2.1m).	

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

🌐 speed cooling

Maison Modulaire, Structure Légère, Carrosseries &
Remorquage, Cabines & Caravanes, Chariot Bateau,
Allucobande & placoplatre, Décoration...

MF: 1418436/A/A/M/000

SPEED COOLING



*room entrance door size (L0.9m*L2.1m)

ELECTRIC PLANT

Supply and installation and electrical installation and wiring, accessories with wall lights installed and running.

-electrical installation :

Socket: flexible cable 3*2.5mm SOMEF-mount-square socket 2p+t Lighting: wall lamp
Flexible cable 3*1.5 - mount and accessories SOMEF.

Kitchen

Supply and installation of a kitchen equipped and installed in MDF laminate (color to customer's choice) with marbled base units plus top units (according to 2D and 3D plan), stainless steel basin with one hole and two gas hob plus extractor hood

SANITARY

Accessories taps brand (SOPAL)

Plumbing: IPALPEX multi-layer //PVC ep1.8mm /// Tangit glue // crimp connection accessories // fixing grout

Sanitary: toilet rear exit brand (SANIMED) plus toilet seat and silent push flush.

Hand washer in kit furnished 40/30 in ceramics.

DELIVERY

Delivery and installation

	PRICE IN DT	PRICE IN USD
PT.TTC	86 000,000 DT	30 565,64 USD

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

📌 speed cooling



Block 2: Training and Meeting room // Salle de formation et de réunion


Designation	Qty
Supply and installation and construction of a multipurpose room in treated and stained light metal structure and frame in red wood and OSB wood and rockwool layer that make the sound and heat insulation and aquatic and wisa composite wood with a total area of 72.96 m ² in the form of modules .	01
COMPOSITION	
*open living room *two toilets M/F	
WALL CLADDING	
-supply and installation and construction of the red wooden frames coated on the outside with 8mm thick OSB wood and on the inside with 50 mm rock wool. External and internal coating of the walls in wood (wisa or ash veneer) thickness 9mm treated and stained (colour according to the customer's choice). -supply and installation of a decorated false ceiling in wood (wisa and brake veneer / treated and stained acajou).	
GROUND COVERING	
-floor in reinforced metal structure treated and tinted with injected polystyrene concrete covered with 9mm wisa wood flooring (treated and tinted).	
ALUMINIUM	
-supply and installation of the windows and doors of the room in single-glazed aluminium (white colour). *room: two windows of dimension (L1.5m*L1m) *Sanitary block: window size (L0.4m*L0.4m). *main entrance door dimension (L1.2M/L2.1M) * Sanitary block inlet door size (L0.8m*L2.1m)	
ELECTRIC PLANT	
Supply and installation and electrical installation and wiring, accessories with wall lights installed and running. -electrical installation : Socket: flexible cable 3*2.5mm SOMEF-mount-square socket 2p+tt Lighting: wall lamp Flexible cable 3*1.5 - mount and accessories SOMEF.	
SANITRY	
Accessories taps brand (SOPAL) Plumbing: multilayer IPALPEX //PVC ep1.8mm /// Tangit glue // crimp connection accessories // fixing grout Sanitary: toilet rear exit brand (SANIMED) plus toilet seat and silent push flush. Hand washer in kit furnished 40/30 in ceramics.	
DELIVERY AND SET UP	

	PRIX EN DT	PRIX EN USD
PT.TTC	44 000,000 DT	15 653,34 USD

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

📺 speed cooling



Block 3: Scientific diving center // Centre de plongée scientifique

Designation	Qty
Supply, installation and construction of a diving centre in treated and tinted light metal structure and framework in red wood and OSB wood and rock wool layer that make the sound and heat insulation and aquatic and wisa composite wood with a total surface area of 15 m ² dimension (L5m/L3m/H2.8m).	01
COMPOSITION	
*open space *two showers plus toilet	
WALL CLADDING	
-supply and installation and construction of the red wooden frames coated on the outside with 8mm thick OSB wood and on the inside with 50 mm rock wool. External and internal coating of the walls in wood (wisa or ash veneer) thickness 9mm treated and stained (colour according to the customer's choice). -supply and installation of a decorated false ceiling in wood (wisa and brake veneer / treated and stained acajou).	
GROUND COVERING	
-floor in reinforced metal structure treated and tinted with injected polystyrene concrete covered with 9mm wisa wood flooring (treated and tinted).	
ALUMINIUM	
-supply and installation of the windows and doors of the centre in single-glazed aluminium (white colour). *window dimension (L1m/L1m) *Sanitary block: window size (L0.4m*L0.4m) *Main entrance door size (L0.9m/L2.1m) * Sanitary block inlet door size (L0.8m*L2.1m)	
ELECTRIC PLANT	
Supply and installation and electrical installation and wiring, accessories with wall lights installed and running. -electrical installation : Socket: flexible cable 3*2.5mm SOMEF-mount-square socket 2p+t Lighting: wall lamp Flexible cable 3*1.5 - mount and accessories SOMEF.	
SANITRY	
Accessories taps brand (SOPAL) Plumbing: multilayer IPALPEX //PVC ep1.8mm /// Tangit glue // crimp connection accessories // fixing grout Sanitary: toilet rear exit brand (SANIMED) plus toilet seat and silent push flush. Hand washer in kit furnished 40/30 in ceramics.	
DELIVERY AND INSTALLATION	

	PRIX EN DT	PRIX EN USD
PT.TTC	16 000,000 DT	5 690,43 USD

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

🌐 speed cooling




Block 4: Eco-Boutique and Cafe // Eco-boutique et café	
Designation	Qty
Supply, installation and construction of a shop in treated and stained light metal structure and frame in red wood and OSB wood and rock wool layer that make the sound and heat insulation and aquatic and composite wood wisa total area 54 m ² dimension (L9m/L6m/H2.8m).	01
COMPOSITION	
*space for collective sale *space for coffee	
WALL CLADDING	
-supply and installation and construction of the red wooden frames coated on the outside with 8mm thick OSB wood and on the inside with 50 mm rock wool. External and internal coating of the walls in wood (wisa or ash veneer) thickness 9mm treated and stained (colour according to the customer's choice). -supply and installation of a decorated false ceiling in wood (wisa and brake veneer / treated and stained acajou).	
GROUND COVERING	
-floor in reinforced metal structure treated and tinted with injected polystyrene concrete covered with 9mm wisa wood flooring (treated and tinted).	
ALUMINIUM	
-supply and installation of windows and doors of the shop and the coffee shop in single-glazed aluminium (white colour). *two windows of dimension (L1m/L1m) *two window size (L1.5m*L1m) *Main entrance door size (L1.2M/L2.1M) *dimensional input door (L0.9m*L2.1m)	
ELECTRIC PLANT	
Supply and installation and electrical installation and wiring, accessories with wall lights installed and running. -electrical installation : Socket: flexible cable 3*2.5mm SOMEF-mount-square socket 2p+t Lighting: wall lamp Flexible cable 3*1.5 - mount and accessories SOMEF.	
DELIVERY AND INSTALLATION	

	PRICE IN DT	PRICE IN USD
PT.TTC	44 000,000 DT	15 653,34 USD

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

🌐 speed cooling




Block 5: Materiel Storage // Stockage de matériel	
Designation	Qty
Supply, installation and construction of a storage space in treated and tinted light metal structure and framework in red wood and OSB wood and rock wool layer that make the sound and heat insulation and aquatic and composite wood wisa total area 18 m ² dimension (L3m/L6m/H2.8m).	01
COMPOSITION	
*empty space	
WALL CLADDING	
-supply and installation and construction of the red wooden frames coated on the outside with 8mm thick OSB wood and on the inside with 50 mm rock wool. External and internal coating of the walls in wood (wisa or ash veneer) thickness 9mm treated and stained (colour according to the customer's choice). -supply and installation of a decorated false ceiling in wood (wisa and brake veneer / treated and stained acajou).	
GROUND COVERING	
-floor in reinforced metal structure treated and tinted with injected polystyrene concrete covered with 9mm wisa wood flooring (treated and tinted).	
door	
-supply and installation of a door in the form of a manual metal curtain of dimension (L2.8m/L2.2m)	
ELECTRIC PLANT	
Supply and installation and electrical installation and wiring, accessories with wall lights installed and running. -electrical installation : Socket: flexible cable 3*2.5mm SOMEF-mount-square socket 2p+t Lighting: wall lamp Flexible cable 3*1.5 - mount and accessories SOMEF.	
DELIVERY AND INSTALLATION	

	PRICE IN DT	PRICE IN USD
PT.TTC	17 000,000 DT	6 047,88 USD

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

🌐 speed cooling



Block 6: First Aid Center for Turtles /Centre de premiers soins pour les tortues

Designation	Qty
Supply, installation and construction of a care centre in treated and tinted light metal structure and framework in red wood and OSB wood and rockwool layer that make the sound and heat insulation and aquatic and wisa composite wood with a total surface area of 15 m ² dimension (L5m/L3m/H2.8m).	01
COMPOSITION	
*empty space	
WALL CLADDING	
-supply and installation and construction of the red wooden frames coated on the outside with 8mm thick OSB wood and on the inside with 50 mm rock wool. External and internal coating of the walls in wood (wisa or ash veneer) thickness 9mm treated and stained (colour according to the customer's choice). -supply and installation of a decorated false ceiling in wood (wisa and brake veneer / treated and stained acajou).	
GROUND COVERING	
-floor in reinforced metal structure treated and tinted with injected polystyrene concrete covered with 9mm wisa wood flooring (treated and tinted).	
door	
-supply and installation of the windows and doors of the treatment centre in single-glazed aluminium (white colour). * window dimension (L1m/L1m) *Main entrance door size (L0.9M/L2.1M)	
ELECTRIC PLANT	
Supply and installation and electrical installation and wiring, accessories with wall lights installed and running. -electrical installation : Socket: flexible cable 3*2.5mm SOMEF-mount-square socket 2p+t Lighting: wall lamp Flexible cable 3*1.5 - mount and accessories SOMEF.	
DELIVERY AND INSTALLATION	

	PRIC IN DT	PRICE IN USD
PT.TTC	15 000,000 DT	5 336,77 USD

☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

📶 speed cooling

Maison Modulaire, Structure Légère, Carrosseries &
Remorquage, Cabines & Caravanes, Chariot Bateau,
Allucobande & placoplatre, Décoration...

MF: 1418436/A/A/M/000

SPEED COOLING



- All construction details (dimension and concept) will be made and approved according to the 2D plans provided by the builder and accepted by the customer.
- (Each modification will be approved by the customer and will be counted outside this estimate (time and price).
- manholes and septic tank will be executed by the client.
- the client must prepare the water and electricity supply
- colours and concept to the customer's choice and Architectural Suite
- connections of water sources, electricity and house equals to the customer's account and out of estimate.

Method of payment :

35% at the order

30% after steel structure construction

30% before installation of doors, windows, sanitary facilities, fittings and flooring.

5% on delivery.

Total TTC/DT	222 000,000	DT
Total TTC/USD	78 947,4	USD

Stopped the present estimate at the sum of "two hundred and twenty-two thousand dinars".

Signature & stamp



☎ 56 033 580 - 54 107 802
26 26 5000 - 26 26 9999

✉ speedcooling007@yahoo.com
📍 Route de Raoued -Sidi Amor- Ariana

📌 speed cooling